| Description | Unit | 45 | 46 | 47 | Total Quantity | Rates In Rupees | Amount Rs. |
|---|---|---|---|---|---|---|---|
| ing & laying precast drain corner cover slab of 200 mm thickness in CM 1:3 including all materials, labour, curing, transportation, loading, unloading etc, complete as per ctions of the Engineer In Charge.( 1.2 x 0.20) Approved Data rate | No's | 234.00 | 98.00 | 47.00 | 379.00 | 10492.00 | 3976468.00 |
| ing & laying precast drain corner cover slab of 200 mm thickness in CM 1:3 including all materials, labour, curing, transportation, loading, unloading etc, complete as per ctions of the Engineer In Charge.( 0.9 x 0.20) Approved Data rate | No's | 545.00 | 147.00 | 108.00 | 800.00 | 8051.00 | 6440800.00 |
| ing & laying precast drain slab of 230 mm thickness in CM 1:3 including cost of ls, labour, curing, transportation, loading, unloading etc, complete as per the ns of the Engineer In Charge.( 1.2 x 0.23) Approved Data rate | Sqm | 8.85 | 19.25 | 8.85 | 36.95 | 5440.98 | 201044.21 |
| ing and resetting of kerb stones.Page No. 270 | No's | 6063.86 | 3696.55 | 4936.35 | 14696.76 | 118.00 | 1734217.68 |
| ing and fixing pre cast solid cement concrete kerb stones made out of M20 with top tom width 114 and 165mm respectively,400mm high and 450mm in length finished M 1:3 plastering and finishing cutting including formwork,curing including cost of ls,labour charges of machinery,loading and unloading,lead and lift,transportation mplete as directed by the Engineer in charge of the work (Excluding GST and Area | No's | 7255.90 | 6721.00 | 5906.74 | 19883.64 | 507.00 | 10081007.73 |
| ing two coats after filling the surface with synthetic enamel paint in all shades on new ed concrete surfaces.Painting Two Coats on New Concrete Surfaces.Item No.8.1,Page Vol III SR 21-22 | Sqm | 2798.71 | 2016.30 | 2278.31 | 7093.32 | 93.50 | 663225.42 |
| | | | | | | Construction Total Amount | 91350491.74 |
| | | | | | | Add GST Charges 18% | 16443088.51 |
| | | | | | | Add Detailed Project Report (DPR) and PMC Charges 2.0% | 2200000.00 |
| | | | | | | Sub Total | 109993580.25 |
| | | | | | | Miscellaneous and unforeseen charges etc.L.S | 6419.75 |
| | | | | | | Grand Total | 110000000.00 |

For CIVIL QUALITY CONSULTANTS & ENGINEERS

Authorised Signatory

**TECHNICAL SANCTION**

Rs: 91350491/- Rs Nine crore thirteen lakhs fifty thousand four hundred is accorded under the head: ninty one only

By CE(R.R.N.), P.N. 22-23

Registered as CE (R.R.N) No: 68/22-23 subject to conditions contained in enclosed memo No: 68/22-23 Date: 8/7/22

TA, CE (R.R.N.)

ನಂ.: AI/22-23 ದಿನಾಂಕ 20/09/2022

ರೂ. 11000000/-

(Eleven crores only)

ಆಡಳಿತಾತ್ಮಕ ಹಿಡಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡಲಾಗಿದೆ.

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ರಾಜರಾಜೇಶ್ವರಿ ನಗರ
ಬಿ.ಬಿ.ಎಂ.ಪಿ

Executive Engineer
RR NAGARA Division
BBMP